

Milton Keynes Datacentre

Address:

St. Neots House, Rockingham Drive Milton Keynes MK14 6LY

Telephone: 0345 119 9911

BOOK A TOUR

Configuration

Number of Data Halls	6
Total Square Feet	45,000
Total Racks	650

Available Rack Configurations

42U or 48U; 600mm x 800mm, 600mm x 1000mm, 600mm x 1200mm, 800mm x 100mm, 800mm x 1200mm; ¼ racks, ½ rack, private cage

Power

Incoming Supply

3.5MW via diverse incoming supplies and transformers to site in an N+1 configuration

UPS Provision

Total capacity of 3.2MW in a 2N+1 configuration

Standby Generator Provision

Total of 4.5MW in an N+1 configuration with 33,000 litres of fuel stored on site, providing a minimum of 24 hours at full load

Power Delivery to Racks

Single or dual 16Amp or 32Amp single phase and 3-phase upon request up to 32Amp

Certifications:



Learn more about our Milton Keynes Datacentre or call 0345 119 9911



Environment

Cooling

Total of 25MW of cooling in an N+1 configuration via chilled water and DX

Fire Protection

Double-knock and Vesda systems, with IG55 and FM200 fire suppression systems

Floor Void

600mm or 800mm dependent on Hall

On-Net Services

Connectivity

Multiple diverse-routed resilient internet site backhaul, dark fibre, 1Mb – multi Gb transit

Carriers

12: BT, KCOM, GEO Networks, Telia, Vtesse, Virgin, CenturyLink Level 3, Colt, TalkTalk, EasyNet, Verizon, Vodafone

Security

CCTV

24 x 7 CCTV recording with 58 cameras and 90-day retention

Access Control

Swipe cards for entry/exit with minimum 12-month retention

Other Systems

Steel perimeter fencing, secure 24x7 manned security entrance with HD CCTV cameras, PAC access controlled into each area of the site

Learn more about our Milton Keynes Datacentre or call 0345 119 9911













